Power support: specify the protected outcome

Buy a documented response to the site's actual power events. A UPS label alone does not identify what stays operational or for how long.

START HERE

Commission a qualified assessment, obtain exact equipment requirements and list every load needed for the proposed bridge, continued operation or controlled shutdown.

PAY MORE WHEN

The accepted design identifies an interruption or power-quality problem that the installed arrangement cannot adequately address for the required equipment.

WATCH THE BUDGET

Include assessment, electrical design, site work, commissioning, batteries, monitoring, routine service and the operating needs of any backup supply.

CHECK THE SUPPORT

Assign responsibility for equipment compatibility, generator handover, recovery, alarms and maintenance. Witness agreed tests under professionally controlled conditions before acceptance.

THREE QUESTIONS FOR THE SUPPLIER

1. Which exact loads and conditions support your runtime claim?

2. Who verifies transfer to backup supply and return to normal?

3. What maintenance and replacement funding preserves the promised capability?

Selected sources: GE HealthCare · GE HealthCare · WHO, World Bank, IRENA and SEforALL

Read the full guide, model comparisons and source notes online →

Reviewed 2026-10-17 · Purchasing guidance; confirm the exact unit, local requirements and support before ordering.