MMS / EQUIPMENT BUYING GUIDE

Hospital equipment readiness guide

Follow the proposed service through an ordinary day and an interruption. Give every essential utility, supply and maintenance dependency a funded owner before shipment.

START HERE

Use the exact installation documents to match equipment with power, oxygen, water, room conditions and storage. Fund the missing enabling infrastructure before adding capacity that cannot operate reliably at the site.

PAY MORE WHEN

Change equipment architecture when it solves a documented constraint: solar-direct-drive vaccine refrigeration can address building-power dependence, while its site, monitoring and installation requirements still need funding.

WATCH THE BUDGET

UAM's ventilator/monitor battery does not power its oxygen concentrator. Airvo is not an oxygen generator. BK200 needs deionized water; dialysis has a separate water-quality system. Include each dependency in the installed cost.

CHECK THE SUPPORT

Carry storage limits through delivery and handover: epoc cards need 15-30°C and Piccolo discs 2-8°C. B51's +32°C upper ambient limit also applies after the installer leaves.

THREE QUESTIONS FOR THE SUPPLIER

1. Which complete utility requirements must our technical team approve?

2. What stops working during our expected power or supply interruption?

3. Who owns replenishment, environmental monitoring and repair after handover?

Selected sources: Gradian Health · Gradian Health · World Health Organization

Read the full guide, model comparisons and source notes online →

Reviewed 2026-10-16 · Purchasing guidance; confirm the exact unit, local requirements and support before ordering.